

# SKAGIT RIVER WOODS

## GREY WATER SUMP DRAIN INSTALLATION

### Installation Requirements

1. Drain Hole must be a minimum of 4 feet deep and 3 feet in diameter. (SCHD)
2. Drain Pipe must be rigid PVC and perforated. (SCHD)
3. Drain Pipe must be 4 inches in diameter, and no less than 3 feet long ( 8 inches wide). (SCHD)
4. Barrels/containers of any kind are not allowed. (SCHD)
5. A "Request for Campsite Construction" and a design plan must be submitted and approved by Caretaker/Manager prior to beginning any digging in your camp site. (SRW)
6. Any grey water sump design other than the one showed on this document will not be permitted unless approved by the Skagit County Health department. (SRW)
7. Once construction on grey water sump has started, the project must be completed within 14 days from the time the hole is dug. The Caretaker/Manager will inspect the construction of the grey water sump hole before fill dirt is put in. (SRW)
8. Recommendation: Add yeast or enzyme to drain pipe periodically to eliminate a build up of food particles and reduce clogging.

